

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of work: Detailed Estimate for the Work Construction of Temporary Emmersion Tank for Lord Ganesh in Ward No. 06 Thanisandra Byatarayanapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2520.00	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	1950.00	Code 0516- Providing Palstic Sheet	sqm	6.00	Rupees Six Only
3	634.80	Providing Stone dust to approch road and near immerssion tank for levelling and to protect not to sliping SI No.23 Code 400 Metal Component	cum	180.00	Rupees One Hundred Eighty Only
4	60.00	Hire Charge of Pumping water 3.5 KL/hr Capacity Pump	hrs	35.00	Rupees Thirty Five Only
5	432.00	Engaging unskilled heavy Mazdoor labour for Guarding and for helping the public to Immersion tank Ganesh Idols and to safe guard the public during the pooja Time	Day s	183.24	Rupees One Hundred Eighty Three and Twenty Four Paise Only
6	3500.0	Hire Charges for Shamiyana Side wall of 8ft Hight (Size175 Rft)	Rtr	17.00	Rupees Seventeen Only
7	300.0	Hire Charges for Armless Plastic Charis	No	4.00	Rupees Four Only
8	300.0	Hire Charges for Wooden Table of size 6ft x 2ft	No	40.00	Rupees Forty Only
9	2200.00	Hire Charge for supplying and running circuit service main with necessary messenger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire	Day s	9.00	Rupees Nine Only
10	136.00	1321 Hire charge of 100 KVA Generator including operator.Fuel transporation nd Handling charges	Hrs	630.00	Rupees Six Hundred Thirty Only
11	30.00	Hire Charges for Flood Lighting Arrangements for the stage and existing Immersion Tank during night time	Eac h Set	285.00	Rupees Two Hundred Eighty Five Only
12	6864.0	Hire Charges for Three Tier Barricading with Casurens poles at 2.50mtrs C/C Vertically and 0.50 mtrs C/C Horizontally with Necessary earth work and labour	Rtr	17.00	Rupees Seventeen Only
13	25850.0	Hire Charge for Shamiyana with Necessary Bambo Poles.Erection charges including transportation -(Size: 40ft x30ft=1200 sqft)	Sft	3.00	Rupees Three Only

NO of corrections - no.1

23/01
E.E. (BTP. DIV)
23/01

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
14	60.00	Hire Charge of Pumping water 3.5 KL/hr Capacity Pump ✓	Hrs	35.00 ✓	Rupees Thirty Five Only ✓

NO of corrections - Nil

[Signature]
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

[Signature]
Chief Engineer
Yerabanka Zone
BBMP, Bangalore - 92